Corrigendum -1

Tender Name : **Pier gap closing and other miscellaneous civil works along the Baiyappanahalli (BYPH) to Challagatta (CLGA) Metro corridor under the SSM Department**

Tender Reference No : **BMRCL/2024-25/BG/WORK_INDENT73**

Sl.No.	Existing Item Description	Read as
1	Covering of gaps between Pier Cap top & Viaduct segment which is of 300 mm height approximately. All the four sides of the Pier Cap have to be covered with Block Masonry of size 400x200x150mm which includes supply of CC Solid Block, cement, Sand, water, fuel for lighting arrangements and for generator, Transportation, Mortar mixing & placing of Blocks, lead, lift, Manpower etc., complete and as directed by Engineer -in-charge. Note: TMHP and generator will be provided by BMRCL	Covering of gaps between Pier Cap top & Viaduct segment which is of 300 mm height approximately. All the four sides of the Pier Cap have to be covered with Block Masonry of size 400x200x150mm which includes supply of CC Solid Block, cement, Sand, water, Generator and fuel for lighting arrangements, and TMHP, Transportation, Mortar mixing & placing of Blocks, lead, lift, Manpower etc., complete and as directed by Engineer -in-charge. Note: TMHP and generator will not be provided by BMRCL (Rate is inclusive of TMHP & Generator)

Manager/SSM/LI
03-04-25.